

WASHINGTON DEPARTMENT OF ECOLOGY
ENVIRONMENTAL ASSESSMENT PROGRAM
FRESHWATER MONITORING UNIT
STREAM DISCHARGE TECHNICAL NOTES

STATION ID: 45F070
STATION NAME: Peshastin Creek at Green Bridge Road
WATER YEAR: 2010
AUTHOR: Tyler W. Burks

Introduction

Watershed Description

Peshastin Creek originates in the snowfields of the eastern slopes of the central Cascade Mountain range and flows into the Wenatchee River at river mile 17. The watershed is bounded by both the Stuart Range (Mount Stuart: 9,415 ft) and the Wenatchee Mountains. Land cover above the gage consists of predominantly coniferous forest, but also includes alpine shrubland, montane grassland, bedrock/talus slopes, and riparian woodlands. A large portion of the lower watershed is used for agricultural production (tree fruit). Mean annual precipitation across the watershed above this gage location is 36 inches (U.S. Weather Bureau, 1965).

Gage Location

The telemetered stream gaging station on Peshastin Creek at Green Bridge Road was installed on September 20, 2002. The gage is located at the Green Bridge Road bridge on the right bank, approximately 1.4 miles upstream of the mouth.

Table 1.

Drainage Area (square miles)	134 (USGS, 2013)
Latitude (degrees, minutes, seconds)	47°33'09" N
Longitude (degrees, minutes, seconds)	120°36'13" W

Discharge

Table 2. Discharge Statistics.

Mean Annual Discharge (cfs)	181
Median Annual Discharge (cfs)	97
Maximum Daily Mean Discharge (cfs)	955
Minimum Daily Mean Discharge (cfs)	11
Maximum Instantaneous Discharge (cfs)	1130
Minimum Instantaneous Discharge (cfs)	9.8
Discharge Equaled or Exceeded 10 % of Recorded Time (cfs)	479
Discharge Equaled or Exceeded 90 % of Recorded Time (cfs)	26
Number of Days Discharge is Greater Than Range of Ratings	0
Number of Days Discharge is Less Than Range of Ratings	0

Note: Statistics displayed in Table 2 may not include values in which the predicted discharge exceeds the range of ratings.

Narrative

Seven discharge measurements were taken, ranging from 21.3 to 725 cfs. Snowmelt runoff slowly began in mid-April, and reached its peak on June 3, 2010, after a gradual warming trend punctuated by rain events. The minimum discharge was recorded during baseflow conditions on October 3, 2008. Discharge was influenced by upstream seasonal irrigation operations, most notably during the month of September.

Error Analysis

Table 3. Error Analysis Summary.

Logger Drift Error (% of discharge)	1.3%
Weighted Rating Error (% of discharge)	14.9%
Total Potential Error (% of discharge)	16.2%

Rating Table(s)

Table 4. Rating Table Summary

Rating Table No.	#6		
Period of Ratings	10/01/2009-09/30/2010		
Range of Ratings (cfs)	3.75-5880		
No. of Defining Measurements	43		
Rating Error (%)	14.9%		

Rating Table No.			
Period of Ratings			
Range of Ratings (cfs)			
No. of Defining Measurements			
Rating Error (%)			

Rating Table No.			
Period of Ratings			
Range of Ratings (cfs)			
No. of Defining Measurements			
Rating Error (%)			

Narrative

The water year began with Table #6 carrying over from the previous water year, and was valid for the remainder of this water year.

Stage Record

Table 5. Stage Record Summary

Minimum Recorded Stage (feet)	0.65
Maximum Recorded Stage (feet)	3.35
Range of Recorded Stage (feet)	2.70
Number of Un-Reported Days	39
Number of Days Qualified as Estimates	33
Number of Days Qualified as Unreliable Estimates	0

Narrative

Unreported days were due to an ice-impacted channel in which the stage-discharge relationship was not valid. The stage record is considered an estimate for 33 days during the water year. These days occurred following a long period of ice-impacted data, prior to the first ice-free gage index observation.

Modeled Discharge

Table 6. Model Summary

Model Type (Slope conveyance, other, none)	Slope Conveyance
Range of Modeled Stage (feet)	3.64 to 6.73
Range of Modeled Discharge (cfs)	1440 to 5880
Valid Period for Model	11/12/2006 to NOW
Model Confidence	+/-1.25%

Surveys

Table 7. Survey Type and Date (station, cross section, longitudinal)

Type	Date
Station Levels	09/19/2007

Activities Completed

--